

General Information

Project Name: _____

Consultant: _____

Item #: _____

Model #: _____

Quantity: _____



Model SICCC-50
Shown w/ optional
Tray Slide

Specifications

Top: 16GA S/S type 300 series with 2" channel edge, all corners welded, ground and polished. S/S channel bracing provided as necessary.

Frame: 14GA S/S multi-formed, fully welded vertical corner uprights.

Mechanical Refrigeration: Unit is refrigerated to maintain a 10 degree temperature with a self contained system and a cold wall surrounding interior liner. Louvered access panels are for proper ventilation. 5' long cord & plug included.

Cabinet: 18GA S/S panels fully insulated with 2 1/2" foamed in place polyurethane, includes removable insulated covers with lift type handles. Cabinet has 1" O.D. drain with valve.

Dispenser: Removable self leveling S/S frame and carrier unit.

Casters: 5" Heavy Duty ball bearing swivel casters, (2) with brakes.

Interlocking Device: As required, quick release latches are provided to join units together.

Product Guide

Modular Ice Cream Counters are convenient and easy to use. These sturdy units are designed for long lasting service.


Units are provided with interlocking devices for quick and easy assembly and disconnecting.

Options

- MST-12** - Tray Slide (Solid) - 12" Wide
- MTT-12** - Tray Slide (Three Bar) - 12" Wide
- MWS** - Work Shelf
- MPWS** - Work Shelf w/ Poly Top
- MPF** - Full Front Panel (Laminate) (ea.)
- MPE** - Full End Panel (Laminate) (ea.)
- MEO** - Convenience Outlets - ____ (ea.)
- M14** - 14GA Top Upgrade
- MKB** - Kick Base - Stainless Steel
- MLF** - Legs w/ Bullet Feet
- Lid Locking Device
- Interlocking Device



DRAWINGS



ICE CREAM COUNTER

Model	Size (W x L x H)	Description	Electrical
□ SICC-35	30 1/2" x 35" x 36"	2.35 C.F.	1/4 HP, 3.5 amps, 120V, 5-15P
□ SICC-50	30 1/2" x 50" x 36"	5.30 C.F.	1/4 HP, 3.5 amps, 120V, 5-15P

RECOMMENDED COUNTER HEIGHT FOR SCHOOLS

- HIGH SCHOOL - STANDARD HEIGHT: 36" COUNTER HEIGHT - 34" TRAY SLIDE HEIGHT
- INTERMEDIATE SCHOOL: 34" COUNTER HEIGHT - 32" TRAY SLIDE HEIGHT
- ELEMENTARY SCHOOL: 32" COUNTER HEIGHT - 30" TRAY SLIDE HEIGHT

Specifications subject to change without notice.

SICC-70 0821